

3 Windows

Windows must be proportioned vertically (minimum 1.8 vertical/1 horizontal). In cement plaster or masonry buildings, windows must be recessed a minimum of four inches (4") from the face of the building and may be simple punched openings or articulated with a surround. In wood buildings, window surrounds must be articulated with a substantial sill, a minimum of five-inch jamb trim and a head trim articulated with a cornice element. Glazing must be broken up into small panes, and muntins must be expressed on the exterior (not sandwiched between two glass panes). See Figures 4.17 - 4.20.

FIGURE 4.17




FIGURE 4.18




FIGURE 4.19
WINDOW IN WOOD




FIGURE 4.20

UNACCEPTABLE WINDOW TREATMENT

